



W. Jefferson - Jones

W JEFFERSON ST

PLEASANT ST

JONES ST

HOLBROOK

SEMINARY ST

Jones - W South

WALNUT ST

Seminary - W South

W SOUTH ST

W South - W Kent

UPDATED NOTICE

GREEN STREET CONSTRUCTION PROJECT

PROJECT EST. TO BEGIN: 08-28-23

Anticipated project completion is November 1, 2023.

Project Contractor: CL Trucking & Excavating, LLC | Ionia, MI

RED ZONE PROJECT SCOPE:

- Water main replacement (including water services to the shut-off near the sidewalk)
- City sanitary sewer replacement
- Storm water drainage improvements
- Street reconstruction (removal of the existing surface, installation of a sand and gravel road base, and application of new pavement)
- Existing curb, gutter, and driveway approaches in the project area will be replaced

YELLOW ZONE PROJECT SCOPE:

- Existing pavement will be milled to a depth of 1 1/2"
- Application of new pavement

GREEN ZONE PROJECT SCOPE:

- Installation of new 7 foot wide sidewalk, "widewalk"



updates ↑

RESIDENT NOTES:

- Please understand all construction timelines are **tentative** and subject to change. Weather conditions, especially rain, can impact the start and/or completion of the construction project.
- You will be notified of any driveway access or utility service interruptions. In the event of a complete street closure, please utilize side streets for parking.
- School starts August 30th, 2023. Bus routes use the South Street/Green Street and Seminary Street/Green Street intersections. Crews will maintain a lane of traffic at both intersections for the buses to complete their routes.
- Trash pick-up will occur on a normal basis and trash bins should be placed on the curb as usual. The contractor will transport trash bins to an adjacent area outside of the construction zone for pick-up. Please label your trash can with your address to ensure it is returned to the correct home (can use tape/marker).

If you have special circumstances, we should be aware of, please contact the Public Services Department at 517-627-2144.

As with any construction project, there will be increased construction traffic, noise, dust, and inconveniences. Vibrations caused by soil compaction during construction may cause slight water discoloration in your home. The discoloration is caused by sediment and natural minerals deposits coming loose in water lines. The discoloration does not pose a safety concern and can be flushed by waiting approximately 30 minutes for crews to stop work, or move from the area, then run cold water in a sink or bathtub until clear. We ask you to be understanding as we work towards completing this important project and thank you very much for your cooperation and patience!

RESIDENT CONTACT:

Viola Dagadu
Project Manager
ENG. Engineering & Surveying
517-974-7988