

SECTION 00920

ADDENDUM

City of Grand Ledge
Ball Field Development Adjacent to Fitzgerald Park PHASE 0

ADDENDUM NO. 1

DATE: 01/23/24

ENGINEER: Eng., Inc.
4063 Grand Oak Drive, Suite A109
Lansing, MI 48911

Drawing Revision No: N/A

Drawing Sheets Issued Herewith: N/A

Bids Due: Wednesday, January 31st, 1:00 p.m. local time Issued to all Plan Holders

This Addendum is part of the Contract Documents and modifies the previously issued Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in rejection of the Bid.

ITEM NO. 1

Replace the third paragraph of section b. Construction of the Special Provision for Machine Grading, Modified from:

“Construction Operations – This work shall consist of the limits of construction; furnishing, hauling, and placing of all required embankment material; roadway excavation, topsoil stripping, grading for placement of topsoil, and disposal of all excess material. The Contractor shall move the excavated material longitudinally and transversely where necessary and remove all excess material from the construction area. This work shall also include providing access to all properties for the duration of the project by placing, moving, maintaining, and removing maintenance gravel on the roadways and at driveways. Maintenance gravel on the roadways and at temporary driveways shall be milled tailings or gravel base and the costs included with this pay item.”

With the following paragraph:

“Construction Operations – This work shall consist of the limits of construction; grading existing native material for placement of topsoil, and disposal of all excess material to the site north of the project limits. The Contractor shall move the excavated material longitudinally and transversely where necessary and remove all excess material from the construction area to the site north of the project limits. This work shall also include providing access to all properties for the duration of the project by placing, moving, maintaining, and removing maintenance gravel on the roadways and at driveways. Maintenance gravel on the roadways and at temporary driveways shall be milled tailings or gravel base and the costs included with this pay item.”

ITEM NO. 2

Below are questions from prospective Bidders with answers following in **boldface**:

- I have a question regarding the owner supplied millings for the Grand Ledge Ball Field Project: It states that we are responsible for trucking the millings from the Grand Ledge DPW to the project site. Are we responsible for loading the millings at the DPW or is the City going to provide a loader and operator to load the millings? – **City of Grand Ledge will load the millings, contractor to coordinate.**
- Are we to assume there is topsoil across the entire site to be stripped? If so, is there a value that should be used? I appears no borings have been included in the specifications. – **There is no topsoil to be stripped.**

- Is topsoil replacement supposed to take place under this contract? The quoted text above states “grading for placement of topsoil”. Is the intent for the contractor to grade and place topsoil or simply grade for placement? If placement is included, shall we use on site material and supplement with imported material or should we plan all imported or all on site material? Do you have a specified depth of topsoil replacement? – **There is no topsoil placement in of this project. City of Grand Ledge will be performing turf establishment outside of the baseball field surface following the machine grading associated with this project. The next phase, Phase 1 includes field turf establishment.**
- Is there supposed to be a high point in the center of the field at the pitcher mound? – **The fine grading within the ball field will be a part of the next phase of this project. (Phase 1)**
- The Final completion date and the dates on the SESC do not align. What is the final completion date? – **Final completion date specified in the bidding documents is to be followed.**

END OF SECTION