

SECTION 00920

ADDENDUM

City of Grand Ledge
Ball Field Development Adjacent to Fitzgerald Park PHASE 0

ADDENDUM NO. 2

DATE: 01/25/24

ENGINEER: Eng., Inc.
4063 Grand Oak Drive, Suite A109
Lansing, MI 48911

Drawing Revision No: N/A

Drawing Sheets Issued Herewith: N/A

Bids Due: Wednesday, January 31st, 1:00 p.m. local time Issued to all Plan Holders

This Addendum is part of the Contract Documents and modifies the previously issued Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in rejection of the Bid.

ITEM NO. 1

Below are questions from prospective Bidders with answers following in **boldface**:

- In looking at the grading for Phase 0 & Phase 1 it appears that the grades given for the outfield turf area and turf area outside of the ballfield for Phase 0 are for the final topsoil elevations. In the addendum it states we are not to spread any topsoil but grade to subgrade elevations and the Phase 1 and city to place the necessary topsoil in all green areas. Am I looking at that correctly? I see in Phase 1 the field topsoil is proposed to be 3" in thickness. With that said, we are to leave room for all topsoil should we hold all green area grades down 3" from what is on the Phase 0 grade in plan? - **The Contractor shall construct grades to 3 inches below proposed grades as shown on the plans (Phase 0) in all future grass areas outside of the proposed parking lot and thickened edge sidewalk to allow for 3 inches of topsoil to be placed by the City or by others in Phase 1.**

END OF SECTION